



LAMIT ROOF PANEL

TRUFAST SCREWS
@ 12" O.C. U.N.O.
W/ 1" MIN
PENETRATION
INTO TOP PLATE

SEALANT

2x TOP PLATE

2x WALL CONSTRUCTION

BEVELED 2x BLOCKING
TOE NAIL W/ 16d NAILS
@ 12" O.C. TOP AND
BOTTOM AFTER ALL
ELECTRICAL HAS BEEN
COMPLETED

PROVIDES ACCESS
FOR ELECTRICAL

OPTIONAL: EPS
WEDGE INFILL OR
EXPANDABLE FOAM

HELPFUL HINT:
WEDGE BEHIND BEVELED BLOCK CAN BE A
GOOD PLACE TO RUN ELECTRICAL WIRES
AFTER SCREWS ARE IN PLACE.

BEVELED 2X WALL TO ROOF

DETAIL NUMBER:

1300

SCALE : NTS

Updated: 3/17/2017

LAMIT INDUSTRIES

STRUCTURAL INSULATED PANELS
FOR THE BUILDING INDUSTRY